

FIRE PREVENTION BUREAU

MONTHLY REPORT

FEBRUARY 2015

New Businesses

505 Warrenville #106 — State Farm Insurance

4900 Lincoln — P&L Motorsports

3033 Ogden #203 — Ventique Labs

6480 College — Tiamo Pizza

6810 RT 53 — The Flooring Store

Construction Projects

5730 College — BU Business Building

4795 Karnes — Arbor Place of Lisle

4314 Lincoln — New retail building

8099 Janes — Woodridge Horizon Senior Living

8201 Janes — Woodridge Park District ARC Building

4100 RT 53 — Morton Arboretum South Farm

3000 Warrenville — Interior lobby remodel

4611 Main — Interior remodel

560 Ogden — Interior remodel

4300 Yackley — Basement remodel

4225 Naper — Café remodel

430 Warrenville — Interior remodel

901 Warrenville #200 & #300 — Interior remodel

1400 Corporetum—Lobby remodel

1001 Warrenville #175 — Interior remodel

Central Park of Lisle — Campus-wide access control system

Points of Interest

CPVC residential sprinkler pipe has very detailed installation instructions that are outlined in the manufacturer' installation manuals. At **Arbor Place of Lisle** (right) 1 1/4" pipe is used in many residential units. The installation manual requires that hangers be spaced no further than five feet apart from drop T's in this size piping. In this picture the hangers on the vertical truss members are greater than five feet apart. For this situation to comply a threaded rod hanger was installed. The system is also required to be braced against upward movement because it operates at 100psi or greater.

Code Enforcement Activities

Activity	Current	YTD
Inspections (Existing)	133	293
Inspections (New)	32	63
Plan Reviews	39	119
Knox Box Updates	45	106
Hazard Investigations	33	63
Code Meetings	21	44
System Follow Ups	90	178

Public Education Activities

Activity	Current	YTD
Fire Safety Talk or Demo	0	2
Fire Station Tour	1	3
Fire Extinguisher Training	0	0
Fire Drill	0	0
Miscellaneous Public Education	0	0

